

51.2 V WALL-MOUNTED HOME ESS BATTERY

Wall-hung residential storage, 5.12 to 15.36 kWh, up to 15 units in parallel with RS485 and CAN to the inverter.

Models	3	Nominal voltage	51.2 V	Capacity range	100 Ah - 300 Ah
Energy range	5,120 Wh - 15,360 Wh	Warranty	5 years	MOQ	10 units (samples from 1)

ELECTRICAL SPECIFICATION

MODEL	FT-48100	FT-48200	FT-48300
Nominal capacity	100 Ah	200 Ah	300 Ah
Nominal energy	5,120 Wh	10,240 Wh	15,360 Wh
Nominal voltage	51.2 V	51.2 V	51.2 V
Charging voltage	58.4 V	58.4 V	58.4 V
Cut-off voltage	40 V	40 V	40 V
Cell configuration	16S	16S	16S
Charge current	100 A	200 A	200 A
Discharge current	100 A	200 A	200 A
Max. peak current (3 s)	200 A	300 A	300 A
Expandability	1-15 in parallel	1-15 in parallel	1-15 in parallel
Communication	RS485, CAN (RS232 optional)	RS485, CAN (RS232 optional)	RS485, CAN (RS232 optional)
Cycle life	6,000 cycles	6,000 cycles	6,000 cycles

MECHANICAL AND ENVIRONMENTAL

MODEL	FT-48100	FT-48200	FT-48300
Terminal	M6	M8	M8
Product size (L×W×H)	675 × 400 × 165 mm	730 × 475 × 255 mm	745 × 570 × 255 mm
Net weight	≈ 51 kg	≈ 87 kg	≈ 135 kg
Package size (L×W×H)	740 × 466 × 275 mm	847 × 542 × 365 mm	847 × 542 × 365 mm
Gross weight	≈ 55 kg	≈ 90 kg	≈ 140 kg

MODEL	FT-48100	FT-48200	FT-48300
Case material	Metal	Metal	Metal
Charging temperature	0 ~ 50 °C	0 ~ 50 °C	0 ~ 50 °C
Discharging temperature	-20 ~ 60 °C	-20 ~ 60 °C	-20 ~ 60 °C

Model codes are shared across form factors. FT-48100, FT-48200, FT-48300 and FT-24300 are used by more than one SafeCloud product family, and the electrical rating is the same while the enclosure, dimensions and weight are not. Always state the form factor together with the model code on enquiries, purchase orders and shipping documents - for example "FT-48300, Wall-mounted" - so the correct enclosure, packing dimensions and freight class are applied.

BMS PROTECTION, CERTIFICATION AND SUPPLY

BMS protection	Overcharge protection, over-discharge protection, over-current protection, short-circuit protection and over-temperature protection.	Certification	UN 38.3, MSDS, CE, FCC. ISO 9001 quality system. Request the certificate that names your model and destination market.
Case material	Metal	Options	Bluetooth or WiFi monitoring module; RS232 in place of RS485
OEM / ODM	Cells, BMS parameters and protocol, enclosure, terminal layout, label and packaging built to specification.	Lead time	Samples 7-10 days. Production 25-35 days, subject to configuration and volume.

Quotation on request. Price depends on model, quantity, application, customisation and delivery terms. Send the model code and form factor, destination country, target quantity and any BMS protocol requirement to info@safecloudpower.com or +86 132 4240 7897. Shenzhen Safecloud Energy Inc., Building 17, Zhongpengcheng Industrial Park, Matian Street, Guangming District, Shenzhen. Production bases in Henan and Anhui.